

What is the construction process and timeline...when will it start?

The construction process takes approximately 16 weeks. It is anticipated that this project will be done in the fall (off-season for the Island).

Synthetic Turf Field Construction Process:

- Top soil is removed to a depth of about 10-12 inches.
- A concrete anchor curb is constructed around the field perimeter.
- Drainage pipe is installed every 20-30 feet.
- A free-draining stone base is installed and laser graded.
- A slope of 0.5% is maintained across the field.
- Track pavement is installed.
- The shock pad is installed on top of the base stone.
- The carpet is installed on top of the shock pad.
- Field lines and markings are permanently installed.
- The carpet is "infilled".
- The track is surfaced with a urethane pavement and structural top coat spray.